PROPOSAL DETAILS

Lake Itasca Park

16030 Andrie St NW, Ramsey, MN 55303, USA

Two existing HOA owned tennis courts - convert to six pickleball courts with reconstruction.

DESCRIPTION	QTY	UNIT PRICE	TOTAL	
Subgrade Correction Allowance Subcut the soil/base material under the existing asphalt court 8" deep and install 8" of new class five rock base.	12,960 Square Feet	\$3.04	\$39,393.94	
Once asphalt is removed, existing sub-base depth and quality will be checked and determination on necessity of subcut and new base will be made. If it is determined that replacement of the base is necessary, the allowance will be adjusted based on the actual amount of sub-cut and new rock base used.				
Asphalt Removal and Re-Pave. Remove existing asphalt and pave 3.5" of new asphalt in two lifts – 2" thick base course and 1.5" wear course.	12,960 Square Feet	\$6.83	\$88,565.66	
Existing tennis posts and footings to be removed and disposed prior to paving. Fencing to be removed and disposed.				
12" maintenances strip to be poured for new perimeter fencing.				
Fencing Install 456 lineal feet of 10' tall chain link fencing, in black, with 2-3/8" line posts, 3" terminal posts, and 1-5/8" top and bottom rails, includes two 4 ft wide doors and one 10 ft. wide door for equipment access;	456 Linear Feet	\$67 ;25	\$30,666.67	
To be installed in maintenance strip,				
ATE Project Management Fee includes sub-contracting and managing the court build. Total is 7% of the managed contracts. This fee covers court design, overhead, site visits, oversight and coordination with sub-contractors.	1 Lump Sum	S11,103,84	\$11,103.84	
portMaster Pickleball Acrylic Surfacing New Asphalt Court) Iew asphalt must cure for a minimum of 28 days rior to surfacing.	.12,960 Square Feet	\$1,53	\$19,781,44	
crylic surfacing includes two coats of acrylic esurfacer, two coats of color, and six sets of 2" ride white pickleball court lines. Owner may select p to 2 colors from the standard color chart.				
later to be provided by owner on-site.				

6 Each

\$1,668.50

\$10,011.00

includes six sets of new pickleball footings.

Water to be provided by owner on-site.

			SUBTOTAL		\$199,522.55	
			TAX	•	\$369.28	
			TOTA		\$199,891.83	
PAYMENT SCHEDULE						
· Name		 			Amount	
Deposit Invoice					\$99,761.28	
Progress Invoice					\$79,313.14	
Completion Invoïce					\$20,817.41	

Payment due upon receipt of invoice. A finance charge of 1 1/2% per month (18% per year) will be charged on any balance over 30 days past invoice date, unless otherwise agreed upon in writing.

- <u>Deposit Invoice</u>: Includes partial payment for materials to surface and partial payment for subgrade correction, asphalt removal and re-pave, and fencing
- Progress Invoice: Includes the remaining balance for the completion of subgrade correction, asphalt removal and re-pave, and fencing
- <u>Completion Invoice</u>: Includes the remaining balance for the completion of surfacing and the supply and installation of pickleball net post systems

Work to be completed in 2026.

Proposed Work Does Not Include: Landscape Restoration, Irrigation Repair/Restoration, Private Utility Eccates/Repairs, Sub-soil Corrections, Erosion Control, Towing Charges, Permits and Fees, Multiple Mobilizations, Surveying or any Unforseen Conditions, Guarantee on drainage or ponding of water on lots with less than 1% slope.